

**NOTICE INVITING QUOTATION**  
 (NIQ No.: NFSU-TC/ENGG-CD/BUILD(SR-ES)/2022-23)

Subject: “Renovation of some part inside the Auditorium Floor of NFSU-Tripura Campus”

Enclosed please find a schedule of items for which your competitive rate is invited. The vendor with lowest quote is required to execute the work under “work contract” mode.

**1. NIQ - Details: -**

1	NIQ No.	
2	About the Institute	NFSU-Tripura Campus is located at VIP Road, Radhanagar, Agartala-799001 (Email id engineeringcell_tripura@nfsu.ac.in). Our is an ethical Institution and we believe in transparency in every facets of work. There is least interference other than quality assurance and timely delivery. There is no need to interact with anyone other than concerned engineer. No material will be allowed to enter the campus from Security gate without passing the same by concerned engineer following technical specifications of the tender. There will be joint measurement of works when completed and bill will be submitted after the joint measurement is accepted. The payment will be made online. Strict quality control will be ensured for the job to be executed as per technical specification and make/brand of materials (in case of any brand or its equivalent specified, sample have to approved in advance ).
3	Name of Work	“Renovation of some part inside the Auditorium Floor of NFSU-Tripura Campus”
5	Estimated Cost	Rs. 65,122/- (Rupees Sixty Five Thousand One Hundred and Twenty Two Only) including GST
6	Completion period	15 Days
7	Start Date of Receiving the Quotations	14 Aug 2024
8	Last date & time of receipt of Quotation	3 Sept 2024, up to 05:30 PM in a Sealed cover only addressed to the “Campus Director”. The bid has to be dropped in the Tender Box kept at the Office on or before the due date & time positively. Tenders may be sent through postal service also. The Quotation shall not be accepted beyond the stipulated date and time under any circumstances whatsoever. Any delay happened in the transition is at the risk of the Vendor and NFSU-TC will not be

responsible.

## Terms & Conditions:

1. The Contractor shall submit the following documents along with quotation in a Sealed cover **super scribed** as “NIQ No.: NFSU-TC/ENGG-CD/BUILD(SR-ES)/2022-23 “Renovation of some part inside the Auditorium Floor of NFSU-Tripura Campus” :-
  - Enlistment Copy with CPWD/PWD
  - PAN (Permanent Account Number)
  - GST (Goods & Service Tax) Registration Certificate
  - Rate Quotation (in the format given at Annexure-A)
2. Payment Terms:
  - The payment will be made after satisfactory and successful completion of the work.
  - The work should be completed as per the specification and direction of Engineer-in-charge.
  - If the work carried out by the contractor is not satisfactory, NFSU-TC shall hold such bills till satisfactory services are provided.
3. Scope of work -
  - Dismantling of Tiles.
  - Providing & Laying 1<sup>st</sup> quality ceramic floor tiles including skirting.
4. The department shall not be responsible for any accident and theft of contractor, manpower and material.
5. Any expenses due to damage/ mishappenings / legal proceeding/compensation occurred due to negligence of contractor in work during the execution of the contract shall be borne by the contractor and the institute shall not be responsible for any such occurrence.
6. Statutory recoveries /taxes as applicable shall be deducted from the payments, as per government norms.
7. **COMPLIANCE WITH REGULATIONS AND INDIAN STANDARDS:**All works shall be carried out in accordance with relevant regulation, both statutory and those specified by the Indian Standards related to the works covered by these specifications.
8. **Mandatory** regulations prescribed by the Government shall be followed by the contractor regarding labour and safety clauses, without any lapse, including those conditions, amended by these departments periodically.

Chief Officer Engineering

(Enclosed: Rate Quotation)

**Annexure A**

National Forensic Sciences University-Tripura Campus					
RATE QUOTATION					
Name of Work: -" Renovation of some part inside the Auditorium Floor of NFSU-Tripura Campus."					
Item No.	Item Description	Unit	Qty.	Rate Quoted by Vendor	
				Unit Rate (INR)	Amount (INR)
1	Dismantling tile work in Floors and roofs and laid in cement mortar including stacking material within 50 meters lead.  For thickness of Tiles 10 mm to 25 mm	Sqm	53.44		
2	Providing and laying 1 <sup>st</sup> quality ceramic floor tiles in different sizes (thickness to be specified by the manufacturer) of 1 <sup>st</sup> quality confirming to IS: 15622-2014 of approved make in colours such as white, Ivory, Grey, Fume Red Brown, laid over 20 mm thick cement mortar 1: 4 (1 cement: 4 fine sand), jointing with grey cement slurry @3.3 Kg/Sqm including pointing the joints with white cement and matching pigment etc all complete as per direction of the Engineer-in-charge.  600 mm x 600 mm in all shades and designs 1 <sup>st</sup> class quality ceramic floor Porcelain tiles.	Sqm	53.44		
				Total Amount Excl. GST (INR)	
				Add GST @18%	
				Total Amount Incl. GST (INR)	

Name of Firm:

E-mail:

Contact No:

Signature & Seal